

OPTICAL SPEED BAR

****From Statewide-Northwest Region STP HRRR(9)**

xx. DESCRIPTION. This work shall consist of furnishing and placing retroreflective optical speed bars at the locations indicated in the Plans and as directed by the Engineer.

The work under this Section shall be performed in accordance with these provisions, the Plans, and Section 646 of the Standard Specifications.

xx. GENERAL REQUIREMENTS. Optical speed bars shall be durable white 450 mm (18 inch) long X 300 mm (12 inch) wide bars applied at the configuration and locations indicated in the Plans.

xx. METHOD OF MEASUREMENT. The quantity of Special Provision (Optical Speed Bar) to be measured for payment will be the number of each bar applied in the complete and accepted work.

xx. BASIS OF PAYMENT. The accepted quantity of Special Provision (Optical Speed Bar) will be paid for at the Contract unit price per each. Payment will be full compensation for furnishing, transporting, handling, and placing the materials specified and for furnishing all labor, tools, equipment, and incidentals necessary to complete the work.

Payment will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
900.620 Special Provision (Optical Speed Bar)	Each