

PEDESTAL MOUNTED PEDESTRIAN SIGNAL HEAD

**\*\*From Statewide-NW Region STP HRRR(17)**

- xx. DESCRIPTION. This work shall consist of furnishing and installing pedestal mounted pedestrian signal heads with ADA push buttons and audible signals at the location(s) indicated in the Plans and as directed by the Engineer.

The work under this Section shall be performed in accordance with these provisions, the Plans, and Section 678 of the Standard Specifications.

- xx. MATERIALS. Materials for Pedestal Mounted Pedestrian Signal Head shall meet the requirements specified in the Plans.

- xx. METHOD OF MEASUREMENT. The quantity of Special Provision (Pedestal Mounted Pedestrian Signal Head, Countdown) to be measured for payment will be the number of each signal head installed in the complete and accepted work.

- xx. BASIS OF PAYMENT. The accepted quantity of Special Provision (Pedestal Mounted Pedestrian Signal Head, Countdown) will be paid for at the Contract unit price per each at each designated intersection. Payment will be full compensation for removing existing signal heads; furnishing, transporting, handling, and installing the materials specified; and for furnishing all labor, tools, equipment, and incidentals necessary to complete the work.

Payment will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
900.620 Special Provision (Pedestal Mounted Pedestrian Signal Head, Countdown) (Main Route @ Side Road)	Each