

10/2/2012

REMOVAL OF TUBULAR MARKER

****From Burlington City/Winooski paving (3 projects)**

- xx. DESCRIPTION. This work shall consist of removing and handling existing tubular marker(s) as specified in the Contract Documents and as directed by the Engineer.
- xx. METHOD OF MEASUREMENT. The quantity of Special Provision (Removal of Tubular Marker) to be measured for payment will be the number of each tubular marker removed in the complete and accepted work.
- xx. BASIS OF PAYMENT. The accepted quantity of Special Provision (Removal of Tubular Marker) will be paid for at the Contract unit price per each. Payment will be full compensation for removing the marker(s); for stockpiling, transporting, and handling the marker(s) as required; and for furnishing all labor, tools, equipment, and incidentals necessary to complete the work.

Payment will be made under:

| <u>Pay Item</u> | <u>Pay Unit</u> |
|---|-----------------|
| 900.620 Special Provision (Removal of Tubular Marker) | Each |