

REMOVE AND REPLACE FLASHING BEACON

****From Enosburg-Richford STP 2939(1)**

- xx. DESCRIPTION. This work shall consist of removing and replacing existing flashing beacon(s) at the location(s) indicated in the Plans and as directed by the Engineer.

The work under this Section shall be performed in accordance with these provisions, the Plans, and Section 678 of the Standard Specifications.

- xx. MATERIALS. Flashing beacon(s) shall meet the requirements of Subsection 752.07.

- xx. CONSTRUCTION REQUIREMENTS. The Contractor shall notify the Engineer a minimum of 48 hours prior to removing and replacing existing flashing beacon(s). While this work is performed, a Uniformed Traffic Officer shall be present to maintain traffic.

After removal, the existing flashing beacon shall be disposed of by the Contractor.

- xx. METHOD OF MEASUREMENT. The quantity of Special Provision (Remove and Replace Flashing Beacon, Aerial Mounted) to be measured for payment will be the number of each flashing beacon removed and replaced in the complete and accepted work.

- xx. BASIS OF PAYMENT. The accepted quantity of Special Provision (Remove and Replace Flashing Beacon, Aerial Mounted) at the location specified will be paid for at the Contract unit price for each. Payment will be full compensation for removing and disposing of the existing beacon; furnishing, transporting, handling, and placing the materials specified; and for furnishing all labor, tools, equipment, and incidentals necessary to complete the work.

Payment for Uniformed Traffic Officer will be made separately under the appropriate Contract item.

Payment will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
900.620 Special Provision (Remove and Replace Flashing Beacon, Aerial Mounted)	Each