

REMOVE EXISTING OVERHEAD LIGHT ASSEMBLY

**\*\*From Montpelier NH 2604(1)S/STP 2618(1)S**

- xx. DESCRIPTION. This work shall consist of removing, and salvaging or disposing, of an existing overhead light assembly(ies) at the location(s) indicated in the Plans and as directed by the Engineer.
- xx. CONSTRUCTION REQUIREMENTS. The Contractor shall remove assembly components in such a manner that salvageable components are not damaged. Components not designated to be salvaged shall be removed from the project and disposed of by the Contractor.
- xx. METHOD OF MEASUREMENT. The quantity of Special Provision (Remove Existing Overhead Light Assembly) to be measured for payment will be the number of each assembly removed in the complete and accepted work.
- xx. BASIS OF PAYMENT. The accepted quantity of Special Provision (Remove Existing Overhead Light Assembly) will be paid for at the Contract unit price per each. Payment will be full compensation for removing, and salvaging or disposing, of assembly components and for furnishing all labor, tools, equipment, and incidentals necessary to complete the work.

Costs associated with providing traffic control and/or flaggers for performing the work will be paid under the appropriate Contract item(s).

Payment will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
900.620 Special Provision (Remove Existing Overhead Light Assembly)	Each