

REMOVING AND RESETTING GROUND/ORNAMENTAL LIGHT ASSEMBLY

****From Barre City FEGC F 026-1(34) C/2**

- xx. DESCRIPTION. This work shall consist of removing and resetting ground and ornamental light(s) at the location(s) indicated in the Contract Documents and as directed by the Engineer.

The work under this Section shall be performed in accordance with these provisions, the Plans, and Section 679 of the Standard Specifications.

- xx. LOCATION. This work is specified for removing and resetting ground and ornamental lights on the Granite Hills Credit Union property that illuminate the Granite Hills Credit Union commercial sign and flag pole in the planting bed.

- xx. GENERAL. The ornamental lights shall be relocated as indicated in the Plans, with guidance from the property owner, and as directed by the Engineer.

- xx. ERECTION OF LIGHT STANDARDS. The Contractor shall coordinate all ground and ornamental light removal and relocation activities with the property owner, and as directed by the Engineer, and shall lock-out breakers and panels as needed to safely perform the work. Care shall be taken in the removal and handling of the lights and appurtenances during relocation. Any components damaged due to Contractor negligence shall be replaced with new components at the Contractor's expense.

The Contractor shall re-use all existing materials to the greatest extent possible for the resetting of ground and ornamental lights. During removal activities of ground and ornamental lights, wiring and conduit shall be cut back to facilitate light installation in new locations as indicated or as directed by the Engineer. If wiring or conduit is damaged by the Contractor during removal, the Contractor shall supply new materials of similar size and type that conform to the National Electric Code and as needed to complete the work to the satisfaction of the Engineer.

- xx. GROUNDING AND TESTING. The reset ground and ornamental lights shall be tested for proper operation after installation. The Contractor shall demonstrate that timers and/or photocells, if so equipped, operate correctly.

- xx. METHOD OF MEASUREMENT. The quantity of Special Provision (Removing and Resetting Ground/Ornamental Light) to be measured for payment will be the number of light assemblies removed and reset in the complete and accepted work.

- xx. BASIS OF PAYMENT. The accepted quantity of Special Provision (Removing and Resetting Ground/Ornamental Light) will be paid for at the Contract unit price per each. Payment will be full compensation for removing lights; installing wiring and conduit; transporting, handling, and resetting lights at the locations indicated in the Plans or as directed by the Engineer; providing

10/2/2012

any new conduit, wiring, hardware, bulbs, and accessories; performing any necessary excavation, backfilling, electrical connections, and testing; and for furnishing all labor, tools, equipment, and incidentals necessary to complete the work.

Removal and resetting of ornamental lights shall be coordinated with the work of REMOVE AND RESET COMMERCIAL SIGN and REMOVE AND RESET FLAG POLE of Section 900.

Payment will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
900.620 Special Provision (Removing and Resetting Ground/Ornamental Light Assembly)	Each