

UTILITY SUPPORT ASSEMBLY

****From Richmond BHF 0209(6)**

- xx. DESCRIPTION. This work shall consist of furnishing and installing utility support hangers for existing sewer and/or water mains, at the locations indicated on the Plans and as directed by the Engineer.

The work under this Section shall be performed in accordance with these provisions, the Plans, and Sections 628 and 629 of the Standard Specifications.

- xx. MATERIALS. Materials for utility support assemblies shall meet the requirements specified in the Plans.

- xx. FABRICATION DRAWINGS. The Contractor shall submit Fabrication Drawings for review and approval in accordance with Subsection 105.03.

- xx. INSTALLATION AND LIABILITY. The utility support assemblies shall be installed as shown on the Plans and as directed by the Engineer. The Contractor shall assume all liability for the installation of utility support assemblies and for disrupting the operation of existing facilities. No interruption in service of the sewer or water mains will be allowed.

- xx. METHOD OF MEASUREMENT. The quantities of Special Provision (Utility Support Assembly, Sewer) and Special Provision (Utility Support Assembly, Water) to be measured for payment will be the number of each utility support assembly installed in the complete and accepted work.

- xx. BASIS OF PAVEMENT. The accepted quantities of Special Provision (Utility Support Assembly, Sewer) and Special Provision (Utility Support Assembly, Water) will be paid for at the Contract unit price per each. Payment will be full compensation for detailing, furnishing, handling, and placing the materials specified; and for furnishing all labor, tools, equipment, and incidentals necessary to complete the work.

Payment will be made under:

| <u>Pay Item</u> | <u>Pay Unit</u> |
|--|-----------------|
| 900.620 Special Provision (Utility Support Assembly, Sewer) | Each |
| 900.620 Special Provision (Utility Support Assembly, Water) | Each |