

ALUMINUM GUARDRAIL, ANODIZED

**\*\*Barre City BHF 6000(15)S**

- xx. DESCRIPTION. This work shall consist of furnishing and erecting anodized aluminum guardrail as shown in the Plans and as directed by the Engineer.

The work under this Section shall be performed in accordance with these provisions, the Plans, and Section 621 of the Standard Specifications.

- xx. FABRICATION. Guardrail shall be anodized to a black satin finish in accordance with ASTM B 580 following fabrication.

- xx. METHOD OF MEASUREMENT. The quantity of Special Provision (Aluminum Guardrail, Anodized 2 Rail) to be measured for payment will be the number of meters (linear feet) installed in the complete and accepted work, measured as shown on the Plans.

- xx. BASIS OF PAYMENT. The accepted quantity of Special Provision (Aluminum Guardrail, Anodized 2 Rail) will be paid for at the Contract unit price per meter (linear foot). Payment will be full compensation for furnishing, transporting, handling, and placing the material specified, and for furnishing all labor, tools, equipment, and incidentals necessary to complete the work.

Payment will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
900.640 Special Provision (Aluminum Guardrail, Anodized 2 Rail)	Meter (Linear Foot)