

BOX BEAM GUARDRAIL, TRUSS

****From Richmond BHF 0209(6)**

- xx. DESCRIPTION. This work shall consist of furnishing and erecting box beam guardrail on the approaches to a steel through truss bridge, at the locations indicated on the Plans and as directed by the Engineer.

The work under this Section shall be performed in accordance with these provisions, the Plans, and Section 621 of the Standard Specifications.

- xx. MATERIALS. Materials for Box Beam Guardrail, Truss shall meet the requirements specified in the Plans.

- xx. CONSTRUCTION REQUIREMENTS. Box Beam Guardrail, Truss shall be installed as detailed on the Plans and as directed by the Engineer.

- xx. METHOD OF MEASUREMENT. The quantity of Special Provision (Box Beam Guardrail, Truss) to be measured for payment will be the number of meters (linear feet) of railing placed in the complete and accepted work, measured within the pay limits designated in the Plans.

- xx. BASIS OF PAYMENT. The accepted quantity of Special Provision (Box Beam Guardrail, Truss) will be paid for at the Contract unit price per meter (linear foot). Payment will be full compensation for detailing, furnishing, handling, galvanizing, and placing the materials specified; and for furnishing all labor, tools, equipment, and incidentals necessary to complete the work.

Payment will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
900.640 Special Provision (Box Beam Guardrail, Truss)	Meter (Linear Foot)