

BOX BEAM GUARDRAIL

**\*\*From Warren-Waitsfield STP 2506(1)**

- xx. DESCRIPTION. This work shall consist of furnishing and erecting box beam guardrail at the locations indicated on the Plans and as directed by the Engineer.

The work under this Section shall be performed in accordance with these provisions, the Plans, and Section 621 of the Standard Specifications.

- xx. MATERIALS. Materials shall meet the requirements specified in the Contract Documents.

- xx. CONSTRUCTION REQUIREMENTS. Box beam guardrail shall be provided and erected to the configuration shown in the Contract Documents.

- xx. METHOD OF MEASUREMENT. The quantity of Special Provision (Box Beam Guardrail w/7 Feet Posts) to be measured for payment will be the number of meters (linear feet) installed in the complete and accepted work, measured from center to center of end posts. An additional 300 mm (1 foot) of guardrail will be allowed for each overhang.

- xx. BASIS OF PAYMENT. The accepted quantity of Special Provision (Box Beam Guardrail w/7 Feet Posts) will be paid for at the Contract unit price per meter (linear foot). Payment will be full compensation for furnishing, transporting, handling, and placing the material specified, and for furnishing all labor, tools, equipment, and incidentals necessary to complete the work.

Payment will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
900.640 Special Provision (Box Beam Guardrail w/7 Feet Posts)	Meter (Linear Foot)