

BRIDGE RAILING, BOX BEAM

**\*\*From Barnard BHO 1444(40)**

- xx. DESCRIPTION. This work shall consist of furnishing and erecting painted bridge railing as shown in the Plans and as directed by the Engineer.

The work under this Section shall be performed in accordance with these provisions, the Plans, and Section 525 of the Standard Specifications.

- xx. INSTALLATION. Railing shall be fascia mounted as detailed in the Plans.

- xx. METHOD OF MEASUREMENT. The quantity of Special Provision (Bridge Railing, Galvanized 2 Rail Box Beam/Fascia Mounted)(Painted) to be measured for payment will be the number of meters (linear feet) of railing used in the complete and accepted work. Measurement will be along the face of railing within the pay limits shown on the Plans and as specified in the Contract Documents.

- xx. BASIS OF PAYMENT. The accepted quantity of Special Provision (Bridge Railing, Galvanized 2 Rail Box Beam/Fascia Mounted)(Painted) will be paid for at the Contract unit price per meter (linear foot). Payment will be full compensation for detailing, furnishing, handling, placing, delineating, galvanizing, applying grease rustproof compound, and painting the railing components; and for furnishing all labor, tools, equipment, and incidentals necessary to complete the work.

Payment will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
900.640 Special Provision (Bridge Railing, Galvanized 2 Rail Box Beam/Fascia Mounted)(Painted)	Meter (Linear Foot)