

BRIDGE RAILING, GALVANIZED 3 RAIL

**\*\*From Bennington AC NH 019-1(53)**

xx. DESCRIPTION. This work shall consist of furnishing and erecting galvanized 3-rail bridge railing as shown in the Plans and as directed by the Engineer.

The work under this Section shall be performed in accordance with these provisions, the Plans, and Section 525 of the Standard Specifications.

xx. MATERIALS. Materials shall meet the requirements specified in the Plans.

xx. CONSTRUCTION REQUIREMENTS. Bridge railing shall be provided and erected to the configuration shown in the Plans.

xx. METHOD OF MEASUREMENT. The quantity of Special Provision (Bridge Railing, Galvanized 3-Rail) to be measured for payment will be the number of meters (linear feet) of rail used in the complete and accepted work. Measurement will be made along the face of rail from end to end or between the pay limits specified.

xx. BASIS OF PAYMENT. The accepted quantity of Special Provision (Bridge Railing, Galvanized 3-Rail) will be paid for at the Contract unit price per meter (linear foot). Payment will be full compensation for detailing, furnishing, handling, placing, delineating, and galvanizing the railing components and for furnishing all labor, tools, equipment, and incidentals necessary to complete the work.

Payment will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
900.640 Special Provision (Bridge Railing, Galvanized 3 Rail)	Meter (Linear Foot)