

DURABLE CROSSWALK MARKING, INLAID THERMOPLASTIC

****From Wilmington AC NH 2504(1)S/HES 010-1(38)**

- xx. DESCRIPTION. This work shall consist of furnishing and installing inlaid thermoplastic durable crosswalk markings at the locations shown in the Plans and as directed by the Engineer.

The work under this Section shall be performed in accordance with these provisions, the Plans, and Section 646 of the Standard Specifications.

- xx. MATERIALS. Materials for crosswalk markings shall meet the requirements specified in the Plans and as recommended by the manufacturer.

Edge line pavement markings shall meet the requirements of Section 646 for Durable White Line, Thermoplastic at the width specified in the Plans.

All materials shall be approved by the Engineer prior to use.

- xx. CONSTRUCTION REQUIREMENTS. The crosswalk shall be constructed to the configuration shown in the Plans, as recommended by the manufacturer and as directed by the Engineer.

Traffic shall only be allowed on the newly constructed crosswalk as recommended by the manufacturer and as directed by the Engineer.

- xx. METHOD OF MEASUREMENT. The quantity of Special Provision (Durable Crosswalk Marking, Inlaid Thermoplastic) to be measured for payment will be the number of meters (feet) of marking applied in the complete and accepted work, as measured along the centerline of the crosswalk.

- xx. BASIS OF PAYMENT. The accepted quantity of Special Provision (Durable Crosswalk Marking, Inlaid Thermoplastic) will be paid for at the Contract unit price per meter (linear foot). Payment will be full compensation for furnishing, handling, and placing the materials specified, including edge line pavement markings, and for furnishing all labor, tools, equipment, and incidentals necessary to complete the work.

Payment will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
900.640 Special Provision (Durable Crosswalk Marking, Inlaid Thermoplastic)	Meter (Linear Foot)