

ORNAMENTAL FENCE

****From Jericho STP FTBR(3)**

- xx. DESCRIPTION. This work shall consist of constructing ornamental fence at the location(s) indicated in the Contract Documents and as directed by the Engineer.

The work under this Section shall be performed in accordance with these provisions, the Plans, and Section 525 of the Standard Specifications.

- xx. GENERAL REQUIREMENTS. Ornamental fence shall be of dimensions and materials similar to the existing fence. Steel components of fencing shall be powder coated black after galvanizing in accordance with ASTM D7803. The Contractor is responsible for visiting the project site to measure existing fencing in order to replicate member sizes, height, spacing, and aesthetic detailing. Post spacing shall match new bridge railing post spacing.

Prior to ordering materials, the Contractor shall submit details for proposed new ornamental fence to the Engineer for approval. The submittal shall include proposed means and methods for attaching the ornamental fence to the new bridge railing.

- xx. METHOD OF MEASUREMENT. The quantity of Special Provision (Ornamental Fence) to be measured for payment will be the number of meters (linear feet) installed in the complete and accepted work. Measurement will be along the top of the fence from outside to outside of end posts for each continuous run of fence.

- xx. BASIS OF PAYMENT. The accepted quantity of Special Provision (Ornamental Fence) will be paid for at the Contract unit price per meter (linear foot). Payment will be full compensation for furnishing, transporting, handling, assembling, placing, galvanizing, and coating the railing components; and for furnishing all labor, tools, equipment, and incidentals necessary to complete the work.

Payment will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
900.640 Special Provision (Ornamental Fence)	Meter (Linear Foot)