

REMOVAL OF TEMPORARY TRAFFIC BARRIER

****From Jericho STP FTBR(3)**

- xx. DESCRIPTION. This work shall consist of removing, loading, delivering, unloading, and stockpiling at a designated location existing temporary traffic barrier as specified in the Contract Documents and as directed by the Engineer.

The work under this Section shall be performed in accordance with these provisions and Section 621 of the Standard Specifications.

- xx. CONSTRUCTION REQUIREMENTS. When no longer needed on the project as determined by the Engineer, the Contractor shall load and deliver the temporary traffic barrier to a location designated by the Engineer.

- xx. METHOD OF MEASUREMENT. The quantity of Special Provision (Removal of Temporary Traffic Barrier) to be measured for payment will be the number of meters (linear feet) of barrier removed in the complete and accepted work.

- xx. BASIS OF PAYMENT. The accepted quantity of Special Provision (Removal of Temporary Traffic Barrier) will be paid for at the Contract unit price per meter (linear foot). Payment will be full compensation for removing, loading, delivering, unloading, and stockpiling the existing temporary traffic barrier and for furnishing all labor, tools, equipment, and incidentals necessary to complete the work.

Payment will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
900.640 Special Provision (Removal of Temporary Traffic Barrier)	Meter (Linear Foot)