

REMOVE AND REPLACE COMPRESSION JOINT SEAL

****From Waterford IM MEMB(31)**

- xx. DESCRIPTION. This work shall consist of removing and replacing compression joint seal material in existing bridge joint(s) at the location(s) indicated in the Plans and as directed by the Engineer.
- xx. MATERIALS. Replacement joint seal material shall be Joint Sealer, Preformed Neoprene meeting the requirements of Subsection 707.06.
- xx. CONSTRUCTION REQUIREMENTS. The Contractor shall remove and dispose of the existing neoprene seal material between joint plates.

The Contract shall install replacement joint seal material in accordance with the manufacturer's recommendations and as directed by the Engineer.

- xx. METHOD OF MEASUREMENT. The quantity of Special Provision (Remove and Replace Compression Joint Seal) to be measured for payment will be the number of meters (linear feet) of compression joint seal removed and replaced in the complete and accepted work, measured along its centerline.
- xx. BASIS OF PAYMENT. The accepted quantity of Special Provision (Remove and Replace Compression Joint Seal) will be paid for at the Contract unit price per meter (linear foot). Payment will be full compensation for removing the existing compression joint seal material; furnishing, handling, transporting, and placing the material specified; and for furnishing all labor, tools, equipment, and incidentals necessary to complete the work.

Payment will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
900.640 Special Provision (Remove and Replace Compression Joint Seal)	Meter (Linear Foot)