

REMOVE AND REPLACE EXISTING APPROACH RAILING

**\*\*From Waterford IM MEMB(31)**

- xx. DESCRIPTION. This work shall consist of removing and replacing existing approach railing at the locations designated in the Plans and/or as directed by the Engineer.

The work under this Section shall be performed in accordance with these provisions, the Plans, and Section 621 of the Standard Specifications.

- xx. CONSTRUCTION REQUIREMENTS. Approach railing shall be replaced in conformance with the configuration shown in the Plans.

- xx. METHOD OF MEASUREMENT. The quantity of Special Provision (Remove and Replace Existing Approach Railing) to be measured for payment will be the number of meters (linear feet) of approach railing removed and replaced in the complete and accepted work.

- xx. BASIS OF PAYMENT. The accepted quantity of Special Provision (Remove and Replace Existing Approach Railing) will be paid for at the Contract unit price per meter (linear foot). Payment will include full compensation for removing and replacing the existing approach railing and for furnishing all labor, tools, equipment, and incidentals necessary to complete the work.

Payment will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
900.640 Special Provision (Remove and Replace Existing Approach Railing)	Meter (Linear Foot)