

TIMBER BACKING FOR GUARDRAIL

****From Charlotte-South Burlington NH 2907(1)**

xx. DESCRIPTION. This work shall consist of furnishing and installing timber backing for guardrail as shown in the Plans and as directed by the Engineer.

The work under this Section shall be performed in accordance with these provisions, the Plans, and Section 621 of the Standard Specifications.

xx. MATERIALS. Materials shall meet the requirements specified in the Plans.

xx. CONSTRUCTION REQUIREMENTS. Timber backing for guardrail shall be installed to the configuration shown on the Plans.

xx. METHOD MEASUREMENT. The quantity of Special Provision (Timber Backing for Guardrail) to be measured for payment will be the number of meters (linear feet) installed in the complete and accepted work, measured within the pay limits shown in the Plans.

xx. BASIS OF PAYMENT. The accepted quantity of Special Provision (Timber Backing for Guardrail) will be paid for at the Contract unit price per meter (linear foot). Payment will be full compensation for furnishing, detailing, transporting, handling, and placing the materials specified, and for furnishing all labor, tools, equipment, and incidentals necessary to complete the work.

Payment will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
900.640 Special Provision (Timber Backing for Guardrail)	Meter (Linear Foot)