

VERTICAL GRANITE CURB, MOUNTABLE

****From Hyde Park HES 030-2(34)**

- xx. DESCRIPTION. This work shall consist of the construction of vertical granite curb as detailed in the Plans and as directed by the Engineer.

The work under this Section shall be performed in accordance with these provisions, the Plans, and Section 616 of the Standard Specifications.
- xx. MATERIALS. Materials shall meet the requirements specified in the Contract Documents.
- xx. CONSTRUCTION REQUIREMENTS. Vertical Granite Curb shall be provided and installed to the configuration shown in the Plans.
- xx. METHOD OF MEASUREMENT. The quantity of Special Provision (Vertical Granite Curb, Mountable) to be measured for payment will be the number of meters (linear feet) installed in the complete and accepted work, as determined along the face of the curb.
- xx. BASIS OF PAYMENT. The accepted quantity of Special Provision (Vertical Granite Curb, Mountable) will be paid for at the Contract unit price per meter (linear foot). Payment will be full compensation for furnishing, transporting, handling, and placing the specified materials, including all excavation, providing, placing, and compacting backfill material when not otherwise specified, mortar for bed and joints, and joint material; cleaning, cutting, fitting, dressing, or stockpiling of curb; and for furnishing all labor, tools, equipment, and incidentals necessary to complete the work.

Payment will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
900.640 Special Provision (Vertical Granite Curb, Mountable)	Meter (Linear Foot)