

WATER BAR

****From Bennington AC NH 019-1(52)**

- xx. DESCRIPTION. This work shall consist of constructing, maintaining, and removing water bars at the locations shown in the Plans and as directed by the Engineer.

The work under this Section shall be performed in accordance with these provisions, the Plans, and Section 653 of the Standard Specifications.

- xx. CONSTRUCTION REQUIREMENTS. Water bars shall be constructed in accordance with the Plans and as directed by the Engineer.

- xx. METHOD OF MEASUREMENT. The quantity of Special Provision (Water Bar) to be measured for payment will be the number of meters (linear feet) installed in the complete and accepted work.

- xx. BASIS OF PAYMENT. The accepted quantity of Special Provision (Water Bar) will be paid for at the Contract unit price per meter (linear foot). Payment will be full compensation for constructing the water bar, including clearing and disposing of trees, brush, stumps, and other obstructions; excavation; compaction; stabilizing with gravel; removing the water bar and restoring the area to the satisfaction of the Engineer; and for furnishing all labor, tools, equipment, and incidentals necessary to complete the work.

Seed, mulch, or any other items necessary to complete the work as specified in the Plans will be paid for under the appropriate Contract item.

Unless otherwise specified in the Contract, payment for the inspection, monitoring, and maintenance of Water Bar will be incidental to Special Provision (Water Bar).

<u>Pay Item</u>	<u>Pay Unit</u>
900.640 Special Provision (Water Bar)	Meter (Linear Foot)