

FLOATING DOCK

**\*\*From New Haven-Weybridge BHO BTN 2005(1)**

- xx. DESCRIPTION. This work shall consist of designing, furnishing, constructing, maintaining, and removing a temporary floating dock and its access in accordance with the Contract Documents and as directed by the Engineer.
- xx. MATERIALS. The Contractor may use any material or combination of materials that will be adequate for a floating dock and its access. The Engineer reserves the right to reject materials and details that are deemed structurally unsafe.
- xx. DRAWINGS. Working Drawings of the proposed floating dock shall be submitted, for documentation purposes only, in accordance with Subsection 105.03. Drawings shall include a plan and typical section indicating size, spacing of components, and materials used.
- xx. DESIGN AND CONSTRUCTION REQUIREMENTS. In designing and constructing a floating dock, the Contractor shall provide a minimum width of 2 m (6 feet) and a minimum length of 6 m (20 feet). The height of the landing surface above the water shall be sufficient for allowing easy access in and out of a canoe. Erosion matting shall be placed between the existing ground and any material used along the access route.
- xx. MAINTENANCE AND LIABILITY. The Contractor shall maintain access to the floating dock to the satisfaction of the Engineer. The Contractor shall assume all liability for the installation, maintenance, and removal of the dock and its access.

Costs for replacing the loss of any part of the dock and its access shall be included in the unit price bid for Contract item 900.645 Special Provision (Floating Dock), except as provided in Subsection 107.18.

- xx. METHOD OF MEASUREMENT. The quantity of Special Provision (Floating Dock) to be measured for payment will be on a lump sum basis in the complete and accepted work.
- xx. BASIS OF PAYMENT. The accepted quantity of Special Provision (Floating Dock) will be paid for at the Contract lump sum price. Payment will be full compensation for designing, detailing, furnishing, constructing, maintaining, and removing the floating dock and its access, and for furnishing all labor, tools, equipment, and incidentals necessary to complete the work.

When the floating dock and its access are accepted and open for public use, a payment of 75 percent of the lump sum price will be allowed. The remaining 25 percent of the lump sum price will be paid when the floating dock and its access have been removed and the site cleaned up to the satisfaction of the Engineer.

Pay Item

Pay Unit

10/1/2012

900.645 Special Provision (Floating Dock)

Lump Sum