00025

PA-01-VT-4066-PW-00025(0) P	
Applicant Name:	Application Title:
LOWELL (TOWN OF)	JCLOC9 Mines Rd.
Period of Performance Start:	Period of Performance End:
06-22-2012	12-22-2013

Bundle Reference # (Amendment #)	Date Awarded

Subgrant Application - FEMA Form 90-91

Note: The Effective Cost Share for this application is 75%

FEDERAL EMERGENCY MANAGEMENT AGENCY
PROJECT WORKSHEET

DISASTER					PROJECT NO.	PA ID NO.	DATE	CATEGORY
FEMA	4066	-	DR	-VT	JCLOC9	019-40525-00	08-06-2012	C

APPLICANT: LOWELL (TOWN OF)	WORK COMPLETE AS OF: 07-15-2012 : 30 %

Site 1 of 1

DAMAGED FACILITY: Mines Rd. (Town of Lowell)	COUNTY: Orleans

LOCATION:	LATITUDE:	LONGITUDE:
Current Version: Mines Rd. A class III rural local asphalt road site 1 is located 220 yds from the intersection with Maple Ridge Rd. Site 2 is located .497 miles from the intersection with Maple Ridge Rd. in the town of Lowell, VT.	44.77887 44.77179	-72.51774 -72.51846

DAMAGE DESCRIPTION AND DIMENSIONS:

Current Version:

During the incident period of May 29, 2012. SITE 1 Heavy rain water flow from a debris blocked culvert, overtopped the roadway causing a road embankment washout of 80ft x 15ft x 5.74ft or 255 cubic yards material lost. The 36" CMP blocked culvert was undamaged. Asphalt roadway was not damaged SITE 2 Heavy rain water flow from a debris blocked culvert overtopped the roadway caused a road embankment washout of 30ft x 12ft x 7.88ft or 105 cubic yards material lost. The 24" CMP blocked culvert was undamaged. Asphalt roadway was not damaged.

SCOPE OF WORK:

Current Version:

WORK COMPLETED The Town of Lowell, using force account labor, material, equipment, rental equipment and contractors repaired the damaged roadway. SITE 1 The 36" CMP culvert was cleared of debris. No other work completed as of July 15, 2012 SITE 2 105 cy. of bank run gravel from the town stockpile was furnished, spread, and graded returning the road embankment back to the predisaster profile. The 24" culvert was cleared of debris. WORK TO BE COMPLETED SITE 1 Town of Lowell is to haul and place 255 cy. of bank run gravel to replace material that was washed away. Work consisted of 14 force account labor and 14 equipment hours. The operational hours provided for the applicant owned equipment are consistent with force account labor documentation. Site is in a flood plan. Codes & Standards was adopted by the Town of March 29, 2011. Applicant has declined to request reimbursement for Direct Administrative Cost. Hazard Mitigation could be identified at this site. Federal funding is contingent upon the applicant acquiring all necessary Federal, State and local permits. Noncompliance with this requirement may jeopardize receipt of Federal Funds. Backup documentation has been reviewed and is on file at the applicant's office. For audit purposes, the applicant must retain records for a period of three years from the date of receipt of final payment

Does the Scope of Work change the pre-disaster conditions at the site? ☐ Yes ☑ No	Special Considerations included? ☑ Yes ☐ No

Hazard Mitigation proposal included? ☑ Yes ☐ No	Is there insurance coverage on this facility? ☐ Yes ☑ No

PROJECT COST

ITEM	CODE	NARRATIVE	QUANTITY/UNIT	UNIT PRICE	COST
1	0000	WORK COMPLETE	0/LS	$ 0.00	$ 0.00
2	9007	LABOR	1/LS	$ 293.53	$ 293.53
3	9009	MATERIAL	1/LS	$ 577.50	$ 577.50
4	9008	EQUIPMENT	1/LS	$ 40.00	$ 40.00
5	9003	CONTRACT COSTS	1/LS	$ 356.25	$ 356.25
6	9004	RENTED EQUIPMENT	1/LS	$ 342.00	$ 342.00
7	0000	WORK TO BE DONE	0/LS	$ 0.00	$ 0.00
8	3021	PIT RUN GRAVEL	255/CY	$ 14.50	$ 3,697.50
9	0909	Hazard Mitigation Proposal	1/LS	$ 3,690.00	$ 3,690.00
				TOTAL COST	$ 8,996.78

PREPARED BY JOSEPH COMBES	TITLE Project Specialist	SIGNATURE
APPLICANT REP. Alden Warner	TITLE Select Board	SIGNATURE