

**GENERAL NOTES**


- MIN. CONCRETE STRENGTH AT 28 DAYS SHALL BE 5,000 PSI.
- MIN. CONCRETE STRENGTH AT STRESS TRANSFER SHALL BE 4,000 PSI.
- REINFORCING STEEL SHALL BE GR-60, ASTM A-615 (AASHTO M31), AND SHALL BE LEVEL II, DUAL-COATED.
- PRESTRESSING STRANDS SHALL CONFORM TO ASTM A-416 (AASHTO M228), AND SHALL CONSIST OF 3/8" x 270 KSI 7 WIRE LOW RELAXATION STRANDS.
- PRESTRESSING STRANDS SHALL EACH BE PULLED TO HAVE A NET TENSION OF 17.2 K (U.N.O.) AFTER ACCOUNTING FOR CHUCK SLIPPAGE. TENSION SHALL BE VERIFIED BY MEASURING STRAND ELONGATION. (SEE EXAMPLE ELONGATION CALCULATION AND TENSIONING PROCEDURE, THIS SHEET).
- ENDS OF PRESTRESSING STRANDS SHALL PROJECT 6" MIN. FROM EACH END OF PANEL.
- THE TOPS OF THE PANELS SHALL BE BROOMED TO A SURFACE ROUGHNESS OF 1/16" (U.N.O.) (BROOM DIRECTION PARALLEL TO STRANDS).
- PANELS SHALL BE HANDLED AND ERECTED USING THE LIFTING INSERTS ONLY. THE MINIMUM SLING ANGLE FROM THE HORIZONTAL SHALL BE 60°. PANELS SHALL BE STORED AND TRANSPORTED WITH TIMBER SUPPORTS WITHIN 2'-0" OF THE PANEL ENDS, UNLESS APPROVED BY J.P. CARRARA & SONS, INC.
- DESIGN MIX: J.P.C. BRIDGE MIX #425M
- QUALITY CONTROL PROCEDURES ARE IN ACCORDANCE WITH PCI REQUIREMENTS, CONTRACT DOCUMENTS & SPECIFICATIONS. J.P. CARRARA & SONS, INC. IS A PCI CERTIFIED PLANT.
- THE ENGINEER WILL BE NOTIFIED AT LEAST 14 DAYS PRIOR TO THE SCHEDULED START OF CASTING AND AT LEAST 2 DAYS BEFORE THE ACTUAL WORK BEGINS.
- CURING METHOD: AS SOON AS THE TOP OF THE PANEL IS FINISHED A COVER OF POLY AND A LAYER OF HOPSOTE, (OR BLUEBOARD) WILL BE PLACED OVER THE PANEL IN A MANNER THAT WILL NOT DISTURB THE BROOM FINISH. THE DESIRED CURING TEMPERATURE RANGE SHALL NOT DROP BELOW 70°. THE TEMPERATURE SHALL BE RECORDED BY AUTOMATIC SENSOR INSTRUMENTS ON GRAPH CHARTS SPACED NOT MORE THAN 50 FEET APART & WILL CONTINUE UNTIL RELEASE STRENGTH IS ACHIEVED (NATURAL CURE WITH NO EXTERNAL HEAT APPLIED). EACH CHART SHALL BE MARKED AND GIVEN TO THE INSPECTOR (IF APPLICABLE).
- THE DRILLING OF HOLES OR USE OF POWER ACTUATED TOOLS ON PANELS SHALL NOT BE PERMITTED.
- THE PANELS SHALL BE ORIENTED AND ERECTED WITH THE MARK-END AS SHOWN ON PLANS.
- THE GENERAL CONTRACTOR IS RESPONSIBLE FOR FORMING THE END OF THE DECK SLAB PRIOR TO CASTING DECK.

**EXAMPLE PRESTRESSING STRAND ELONGATION CALC. AND TENSIONING**  
(NOT TO BE USED FOR CONSTRUCTION)


SIZE & GRADE: 3/8" x 270 KSI  
 AREA: 0.085 IN<sup>2</sup>  
 TENSION: 17,200 LBS. EACH STRAND  
 GRIP TO GRIP: 120'-6" = 120.5'  
 $E_s = 28,600,000$  PSI (ASSUMED FOR THESE CALCULATIONS; VALUE TO BE OBTAINED FOR STRAND SPOOL ACTUALLY USED)  
 EXAMPLE:  $\Delta = \frac{PL}{AE} = \frac{(17,200 - 3,000) \times 120.5 \times 12}{0.085 \times 28,600,000} = 8.45"$   
 THEREFORE: TOLERANCES:  $\pm 5\%$   
 $\Delta$  UPPER LIMIT =  $1.05 \times 8.45" = 8.87" = 8 \text{ } 7/8"$   
 $\Delta$  LOWER LIMIT =  $0.95 \times 8.45" = 8.03" = 8"$   
 EXTRA FORCE REQUIRED TO COMPENSATE FOR 1/2" CHUCK SLIPPAGE:  
 $\Delta P = \frac{0.5 \times 17,200}{8.45} = 840$  LBS.  
 TOTAL TENSIONING FORCE = 17,200 + 840 = 18,040 LBS.

**STRAND TENSIONING PROCEDURE:**


- PULL EACH STRAND INITIALLY TO 3,000 LBS. \* AND MARK STRAND.
  - THEN PULL EACH STRAND TO A TOTAL TENSION OF 18,040 LBS. \* AND MEASURE ELONGATION AFTER SEATING. IT MUST BE BETWEEN 8" AND 8 7/8".
- \* NOTE: FORCES READ ON STRESSING JACK GAUGES MUST BE MADE TO CORRESPOND TO ABOVE VALUES BASED ON CALIBRATION DATA FOR SPECIFIC JACK USED.




**1 PRESTRESSED STAY-IN-PLACE FORM PANEL LAYOUT**  
1/8" = 1'-0"




**2 TRANSVERSE SECTION**  
3/8" = 1'-0"



**A SECTION**  
1 1/2" = 1'-0"




**TYP. STORAGE & SHIPPING DUNNAGE LOCATIONS**  
N.T.S.




**LEVELING EMBED & JACK DETAIL**  
N.T.S.

5-12-14 REVISED AS NOTED


APPROVAL STAMP:	<b>J.P. CARRARA &amp; SONS INC.</b> A.L. ST. ONGE CONTRACTOR, INC. Precast & Prestress Manufacturer 2444 CASE STR., MIDDLEBURY, VERMONT 05753 Phone: (802)388-6361 Fax: (802)388-9010	
	STATE OF VERMONT AGENCY OF TRANSPORTATION COUNTY OF LAMOILLE	DATE: APRIL 10, 2014 SCALE: NOTED
	TOWN OF HYDE PARK VT ROUTE 15 (MINOR ARTERIAL) BRIDGE NO.: 42 PROJECT NO.: STP CULV(26)	CHKD: - DFTM: B.L. JOB NO: 23427-014
	<b>SUPERSTRUCTURE PLAN &amp; SECTIONS</b> DWG. NO: <b>F1</b>	




DECK PANEL - 'HP-1'  
1/2" = 1'-0"



DECK PANEL - 'HP-2'  
1/2" = 1'-0"



DECK PANEL SECTION - 'A-A'  
1" = 1'-0"



DECK PANEL SECTION - 'B-B'  
1" = 1'-0"



DETENSIONING SCHEDULE  
N.T.S.

SHOP NOTE:  
INSTALL LEVELING JACK INSERTS FLUSH TO FORM AT ENDS OF PANELS ON FIRST TWO (2) STRANDS AT EA. SIDE OF PANEL

MARK:	HP-1	QTY.:	8	WT.:	1.4 T	VOL.:	0.69 cy
MARK:	HP-2	QTY.:	52	WT.:	1.4 T	VOL.:	0.69 cy
MARK:	-	QTY.:	-	WT.:	-	VOL.:	-

MATERIAL LIST / PANEL				
ITEM	DESCRIPTION	QTY./PANEL		
		HP-1	HP-2	-
1	#3 x 7'-10" (LEVEL II, DUAL COATED)		16	
2	#3 x 8'-11" (LEVEL II, DUAL COATED)	16		
3				
4				
5				
6	1T x 2 5/8" SWIFT LIFT LIFTER (GALV.)	4	4	
7				
8	LEVELING JACK EMBED INSERTS	4	4	
9				
10				
11				

APPROVAL STAMP:

**J.P. CARRARA & SONS INC.** A.L. ST. ONGE CONTRACTOR, INC.  
 Precast & Prestress Manufacturer CONTRACTOR  
 2464 CASE CIR., MIDDLEBURY, VERMONT 05753 Phone: (802) 388-6361 Fax: (802) 388-9010 MONTGOMERY, VERMONT

STATE OF VERMONT AGENCY OF TRANSPORTATION COUNTY OF LAMOILLE DATE: APRIL 10, 2014  
 SCALE: NOTED

TOWN OF HYDE PARK VT ROUTE 15 (MINOR ARTERIAL) CHKD: - DFTM: B.L.  
 BRIDGE NO.: 42 PROJECT NO.: STP CULV(26) JOB NO: 23427-014

PRESTRESSED S.I.P. FORM PANEL DETAILS DWG. NO: P1