

Revised February 23, 2015

Special Provisions for: Colchester STP 5600(12)

1. LABOR SUPPLY. Available workers for this Contract may be obtained from Manager, Employment & Training, Burlington, VT. The latest edition of the DBE Registry can be obtained from the Office of Civil Rights and Labor's Webpage at the following address: www.aot.state.vt.us/CivilRights/default.htm. Contractors that do not have access to the internet may obtain a copy from the Office of Contract Administration upon request.
2. CONTRACT COMPLETION DATE. This Contract shall be completed on or before October 23, 2015.
3. NOTICE TO BIDDERS - CONCURRENT CONSTRUCTION. The Contractor is hereby notified that a concurrent municipal construction project will be in progress within the area of this project during its construction. The Town of Colchester will have Mill Pond Road under construction from the end of the STP 5600(12) project (Station 16+75) to the intersection of VT 2A. Information regarding this project is available from Town of Colchester Project Manager Kevin McAleer [Tel.: (802)264-5639; kmcaleer@colchestervt.gov].

There will be minimal access to the STP 5600(12) project site from the east end of the project. The Town of Colchester will be restricting traffic during their phase of work. The Town of Colchester will have the road closed from Station 16+75 to VT 2A during working hours. The road will be open to one lane of traffic from the end of their work day until the following morning. At the end of each day, the roadway will consist of either the entire subbase cross section to the top of the dense graded gravel or the existing pavement for a minimum of one lane.

It is the responsibility of the Contractor to communicate with the Town of Colchester's contractor for the Mill Pond Road reconstruction project while performing work that connects or overlaps into the municipal project. See Special Provision No. 4 for additional information and requirements.

There will be no extra compensation paid to the Contractor for any inconvenience caused by working around this or other project(s).

4. NOTICE TO BIDDERS - WORK REQUIREMENTS. The Contractor is hereby notified of the following requirements for completing the work under this Contract:
 - (a) The Contractor shall install the catch basins, inlet piping, and discharge piping prior to starting work on Bridge No. 12. Following installation of piping that crosses Mill Pond Road, Mill Pond Road shall be at existing grade to allow property owner access to drive at Station 15+67 RT. This work shall be completed by May 1, 2015.
 - (b) The Contractor will be responsible for placing all pavement from the Begin Approach Station to the Begin Bridge Station. The Contractor will be responsible for placing only the first lift of pavement from the End Bridge Station to the End of Project Station.
 - (c) The Town of Colchester's contractor will be responsible for placing the final lift of pavement from the End Bridge Station to the end of the municipal project.

Special Provision (Bituminous Concrete Pavement, Small Quantity) mixture approved by the Engineer for use in correcting deficiencies in the base course constructed as part of the Contract will not be paid for as Special Provision (Bituminous Concrete Pavement, Small Quantity), but will be incidental to the Contract item for the specified type of base course.

Special Provision (Bituminous Concrete Pavement, Small Quantity) mixture used to correct deficiencies in an existing pavement or to adjust the grade of a bituminous concrete surface completed under the Contract will be paid for at the Contract unit price for Special Provision (Bituminous Concrete Pavement, Small Quantity).

Payment will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
900.650 Special Provision (Mat Density Pay Adjustment, Small Quantity) (N.A.B.I.)	Lump Unit
900.650 Special Provision (Mixture Pay Adjustment) (N.A.B.I.)	Lump Unit
900.680 Special Provision (Bituminous Concrete Pavement, Small Quantity)	Ton

ADDITIONAL SPECIAL PROVISION

105. NOTICE TO BIDDERS - BUILDING INSPECTION. For the protection of the Contractor and all property owners, before beginning any construction activities, the Contractor shall video inspect, inside and out, potentially affected properties within the project limits. Buildings within 100 feet of the project limits that may be affected by any construction operations shall be included. The Contractor's insurer shall notify the Engineer when the video is complete and shall be available upon request by the Agency.

Upon completion of project construction, the Contractor's Insurer shall again completely inspect, inside and out, and make a complete video CD record of all buildings as part of the inspection. A written copy of the complete inspection report shall be delivered to the Engineer by the Contractor. The video shall remain the property of the Contractor's insurer for one year after the project completion date.

All members of the Insurer's inspection team shall personally identify themselves to the Engineer prior to beginning each inspection.

All costs involved in performing this work will be considered incidental to all Contract items.