

Hand-placed bituminous concrete material placed less than 12.5 mm (½ inch) thick will not be measured for payment.

When any portion or all of Special Provision (Hand-Placed Bituminous Concrete Material, Drives) is removed from the project under any provisions of the Contract or as directed by the Engineer, no payment will be made for the removal, disposal, or replacement of said material.

- 118. BASIS OF PAYMENT. The measured quantity of Special Provision (Hand-Placed Bituminous Concrete Material, Drives) will be paid for at the Contract unit price per square meter (square yard). Payment shall be full compensation for furnishing, mixing, hauling, placing, compacting, and finishing the material specified and for furnishing all labor, tools, equipment, and incidentals necessary to complete the work.

Emulsified asphalt used as specified and backfill material meeting the requirements specified in the Plans will be considered incidental to Special Provision (Hand-Placed Bituminous Concrete Material, Drives).

When not specified for payment under separate Contract item(s), the costs of placing subbase material, cleaning existing paved surfaces, including power equipment, and for filling joints, cracks, and holes will not be paid for directly, but will be considered incidental to Special Provision (Hand-Placed Bituminous Concrete Material, Drives).

Payment will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
900.675 Special Provision (Hand-Placed Bituminous Concrete Material, Drives)	Square Yard

ADDITIONAL SPECIAL PROVISION

- 119. NOTICE TO BIDDERS - PLAN SHEET MODIFICATIONS. The Contractor is hereby notified of the following Plan Sheet modifications:

- (a) Sheet 2 - PRELIMINARY INFORMATION.

- (1) PILE DRIVING AND TESTING REQUIREMENTS, Note No. 3 MAXIMUM PILE TIP ELEVATION, is hereby modified by deleting the number "503.00" and replacing it with the number "498.00".

- (b) Sheet 4 - PROJECT NOTES.

- (2) H-PILES, Note No. 42, is hereby modified by deleting the number "286" and replacing it with the number "440".